



RAJIV GANDHI UNIVERSITY OF KNOWLEDGE TECHNOLOGIES
(A.P Government Act 18 of 2008)

Nuzvid, RGUKT-campus, Krishna District, Andhra Pradesh-521202

Tele No: 08656-235557.

E-mail Id: ao.nuz@rgukt.in

Ref. No: RGUKT/NUZ/Proc/NIQ/CIVIL/RFT-H/16 -17

Date: 10.03.2017

To

All Interested vendors

Dear Sir/ Madam,

SUB: NOTICE INVITING QUOTATION FOR REPAIRING OF DAMAGED FLOOR TILES IN BOYS & GIRLS HOSTEL AT RGUKT – NUZVID.

The Administrative Officer, RGUKT- Nuzvid invites quotations for REPAIRING OF DAMAGED FLOOR TILES IN BOYS & GIRLS HOSTEL -RGUKT- Nuzvid, in Single bid as indicated, in sealed cover, is hereby invited to reach the undersigned on or before 23.03.2017. Kindly quote your lowest price including taxes & transportation.

The Details are as follows:-

See enclosure

Please Note-

01. Address of the firms submitting the quotation and the Officer, to whom the quotation is addressed, must appear distinctly on the sealed cover as under. Quotation in must be sealed cover should reach or before 23.03.2017, by speed post/ Courier service/by person.
02. The following must be clearly written on the outer sealed cover irrespective of single bid. Without sealed cover, the quotation will not be accepted.

QUOTATION FOR SUPPLY OF FLOOR TILES WORK TO RGUKT- NUZVID
NIQ REF NO: RGUKT/NUZ/PROC/NIQ/CIVIL/2016-17, Date: 10.03.2017

To
The ADMINISTRATIVE OFFICER
RGUKT – NUZVID
KRISHNA (DIST) – A.P. – 521202

03. There is no Quotation document fee and Quotation document is to be downloaded from our website given below. www.rguktnuz.in/tenders or www.rguktn.ac.in/tenders
04. **Validity:** Quoted rates must valid for 120 days

05. **Delivery:** Unless otherwise stated delivery of goods at RGUKT-Nuzvid, will have to be maximum within 15days
06. **Firm Registration Document and PAN Account No.** copy of the document to be furnished
07. **CST/VAT/TIN No.** must appear in the Invoice/bill
08. All aspects of safe delivery shall be the exclusive responsibility of the vendor
09. **Late and delayed quotation:** Late and delayed tender will not be considered. In case any unscheduled holiday occurs on prescribed closing/opening date, the next working day shall be the prescribed date of closing/opening.
10. **Bid not transferable:** The bid documents are not transferable and the seal and signature of the authorized official of the firm's must appear on all the papers and envelopes submitted.
11. **Payment:** Payment will be made within 30 days from the date of successful delivery and acceptance of goods at RGUKT-Nuzvid, generally through RTGS / FUND TRANSFER. Following information must be clearly written in the quotation for RTGS / FUND TRANSFER: -
 - (a) Name of the Firm with complete postal address
 - (b) ACCOUNT No
 - (c) Name of the Bank with Branch where the Account exist
 - (d) IFSC CODE
 - (e) PAN No:
12. Kindly read both the Instructions and Terms properly and see that instructions and terms are fully understood and complied. No correspondence shall be entertained in case your quotation is rejected on ground of not complying with our instructions, terms and conditions. In case of doubt please contact us at 8333981200 or the Administrative Office.

13. INSTRUCTION TO BIDDERS

A) Important Date and Time:

(i) Last date & Time of receipt of Tender: **23.03.2017, (1700 HRS)**

(ii) Time of opening Tender: **24.03.2016, (1500 HRS)**

(iii) Venue of Bid opening: Office of the Administrative Officer's, RGUKT- Nuzvid.

Sd/-

Administrative Officer

REPAIRING OF DAMAGED FLOOR TILES IN BOYS & GIRLS HOSTEL

S.No.	Description of Item	Measurements						Contents	Unit	Rate	Per		Amount
		No.		L	B	D							
1	Dismantling, clearing away and carefully stacking useful materials for re-use and disposal of unserviceable materials with 100m lead as directed by Executive Engineer duly taking actual pre-measurements before dismantling including all labour charges , overheads & contractor profit etc., complete												
	For laying of line	1	x	1700	0.40	0.40	0.06	16.32	cum		1	cum	
2	Granolithic Concrete flooring 20 mm thick with (1:1:2), using 6mm to 12 mm size hard granite machine crushed metal and screened sand laid over CC bed already laid or RCC roof slab, in alternate panels of size not exceeding 1.50 m x 1.50 m, using glass strips and finishing the top surface to required smoothness and slopes and thread lining including cost of all materials like cement, metal sand and water and overheads & contractors profit complete for finished item of work. (APSS No.701 & 710)												
	In Ground Floor	1	x	120	0.40	0.40	-	19.20	sq.mt		1	sq.mt	
	In First floor	1	x	422	0.40	0.40	-	67.52	sq.mt		1	sq.mt	
	In Second floor	1	x	658	0.40	0.40	-	105.28	sq.mt		1	sq.mt	
	In Third floor	1	x	500	0.40	0.40	-	80.00	sq.mt		1	sq.mt	
	Total (A)												
3	Add VAT 5% on (A)									0.05			
4	TOTAL ESTIMATE COST												