



RAJIV GANDHI UNIVERSITY OF KNOWLEDGE TECHNOLOGIES

(A.P Government Act 18 of 2008)

Nuzvid, RGUKT-campus, Krishna District, Andhra Pradesh-521202

Tele No: 08656-235557.

E-mail Id: ao.nuz@rgukt.in

Ref. No: RGUKT/NUZ/Proc/NIQ/Iron Grills/16 -17

Date: 08.03.2017

To

All Interested vendors

Dear Sir/ Madam,

SUB: NOTICE INVITING QUOTATION FOR FIXING OF IRON GRILLS AROUND COOLERS-I1 & I2 BOYS HOSTEL AT RGUKT – NUZVID.

The Administrative Officer, RGUKT- Nuzvid invites quotations for IRON GRILL WORK- RGUKT- Nuzvid, in Single bid as indicated, in sealed cover, is hereby invited to reach the undersigned on or before 20.03.2017. Kindly quote your lowest price including taxes & transportation.

The Details are as follows:-

See enclosure

Please Note-

01. Address of the firms submitting the quotation and the Officer, to whom the quotation is addressed, must appear distinctly on the sealed cover as under. Quotation in must be sealed cover should reach or before 20.03.2017, by speed post/ Courier service/by person.
02. The following must be clearly written on the outer sealed cover irrespective of single bid. Without sealed cover, the quotation will not be accepted.

QUOTATION FOR SUPPLY OF IRON GRILL TO RGUKT- NUZVID
NIQ REF NO: RGUKT/NUZ/Proc/NIQ/CIVIL/2016-17, Date: 08.03.2017

To
The ADMINISTRATIVE OFFICER
RGUKT – NUZVID
KRISHNA (DIST) – A.P. – 521202

03. There is no Quotation document fee and Quotation document is to be downloaded from our website given below. www.rguktnuz.in/tenders or www.rguktn.ac.in/tenders
04. **Validity:** Quoted rates must valid for 120 days
05. **Delivery:** Unless otherwise stated delivery of goods at RGUKT-Nuzvid, will have to be maximum within 15days

06. **Firm Registration Document and PAN Account No.** copy of the document to be furnished
07. **CST/VAT/TIN No.** must appear in the Invoice/bill
08. All aspects of safe delivery shall be the exclusive responsibility of the vendor
09. **Late and delayed quotation:** Late and delayed tender will not be considered. In case any unscheduled holiday occurs on prescribed closing/opening date, the next working day shall be the prescribed date of closing/opening.
10. **Bid not transferable:** The bid documents are not transferable and the seal and signature of the authorized official of the firm's must appear on all the papers and envelopes submitted.
11. Payment: Payment will be made within 30 days from the date of successful delivery and acceptance of goods at RGUKT-Nuzvid, generally through RTGS / FUND TRANSFER. Following information must be clearly written in the quotation for RTGS / FUND TRANSFER: -
 - (a) Name of the Firm with complete postal address
 - (b) ACCOUNT No
 - (c) Name of the Bank with Branch where the Account exist
 - (d) IFSC CODE
 - (e) PAN No:
12. Kindly read both the Instructions and Terms properly and see that instructions and terms are fully understood and complied. No correspondence shall be entertained in case your quotation is rejected on ground of not complying with our instructions, terms and conditions. In case of doubt please contact us at 08656- 235557 or the Administrative Office.

13. INSTRUCTION TO BIDDERS

A) Important Date and Time:

(i) Last date & Time of receipt of Tender: **20.03.2017, (1700 HRS)**

(ii) Time of opening Tender: **21.03.2016, (1500 HRS)**

(iii) Venue of Bid opening: Office of the Administrative Officer's, RGUKT- Nuzvid.

Sd/-

Administrative Officer

FIXING OF IRON GRILL AROUND THE COOLER AREA IN I-1 AND I-2 BOYS HOSTEL BUILDING

S.No.	Description of Item	Measurements					Contents	Unit	Rate	Per	Amount
		No.		L	B	D					
1	Dismantling, clearing away and carefully stacking useful materials for re-use and disposal of unserviceable materials with 100m lead as directed by Executive Engineer duly taking actual premeasurements before dismantling including all labour charges , overheads & contractor profit etc., complete										
	Floor dismantling for placing of frame	4	x	2	0.23	-	2.10	3.86	sq.mt	1	sq.mt
	for providing of water point in Third floor	4	x	1	1.50	1.20	-	7.20	sq.mt	1	sq.mt
2	Providing Mild Steel structural steel Angles, Channels & I Sections of all sizes as per IS-1161, Labour charges for fabricating all heavy steel works like Trusses, Stanchions, Heavy Beams and Girders including cost of welding rods, power charges, etc excluding cost of fixing in position, for fixing heavy iron grills,gates Trusses, Stanchions, Heavy Beams and Girders erecting in position and fixing by using chain pulley blocks, Derek pole arrangements and cranes etc., complete in position INCLUDING ALL WASTAGES										
					L	UnitWeight					
	for making of frame with ISA 25x25x5mm in horizontal direction	4	x	2	10.20	1.80	-	146.88	Kg	1	Kg
	for making of frame with ISA 25x25x5mm in vertical direction	4	x	8	3.20	1.80	-	184.32	Kg	1	Kg
	for making of panels with ISSQ 10mm horizontal direction	4	x	32	3.80	0.80	-	389.12	Kg	1	Kg
	for making of panels with ISSQ 10mm vertical direction	4	x	37	3.20	0.80	-	378.88	Kg	1	Kg
	Steel for making of aldrops, tower bolt, handles, bolts	4	x	1	1.00	1.00	-	50.00	kg	1	kg
3	Brick masonry for panel walls in superstructure with CM (1:5) prop: (Cement : Screened sand) using common burnt clay bricks of class as per Table- I of IS:1077-1992, Non- Modular or traditional size 23 x 11 x 7 cms from approved source having minimum crushing strength of 40 Kg/Sqcm. including cost and conveyance of all materials like cement, screened sand, bricks, water etc., to site, including sales & other taxes on all materials and such as labour charges, like mixing cement mortar, scaffolding charges, constructing masonry, lift charges, curing, etc.,and overheads & contractors profit complete for finished item of work. (APSS No. 501 & 504).										
	around cooler area at floor level	4	x	1	2.70	0.23	0.23	0.57	cum	1	cum
	around the water point	4	x	1	2.70	0.23	0.23	0.57	cum	1	cum
	to water point pedestal	4	x	2	0.23	0.23	0.70	0.30	cum	1	cum
	to close the entrance to terrace floor	2	x	4	1.20	0.23	2.10	4.64	cum	1	cum

4	Plain Cement Concrete (1:3:6) nominal mix using 20mm size graded machine crushed hard granite metal (coarse aggregate - as per IS 383 - 1970 and IS 2386 Part 1 to Part 8) from approved quarry including cost and conveyance of all materials like cement, fine aggregate(sand), coarse aggregate, water etc. to site, including sales & other taxes on all materials and including all charges for mixing, laying concrete in position, curing etc., & lift charges, and overheads & contractors profit for Bed Blocks & Hold Fast for finished item of work. (APSS No. 402)												
	at water point pedestal area	2	x	2	1.50	1.2	0.23	1.66	cum		1	cum	
5	Plastering 12mm thick single coat in CM(1:5) using screened sand including cost and conveyance of all materials like cement, sand, water etc., to site, including sales & other taxes on all materials, and all operational, incidental charges on materials and including cost of all labour charges for mixing mortar, finishing, curing as directed by Engineer-in-charge etc., and overheads & contractors profit complete for finished item of work.(SS 901,903 & 904)												
	around cooler area at floor level	4	x	3	2.70	-	0.23	7.45	sq.mt		1	sq.mt	
	around the water point	4	x	3	2.70	-	0.23	7.45	sq.mt		1	sq.mt	
	to water point pedestal	4	x	4	0.23	-	0.70	2.58	sq.mt		1	sq.mt	
	to close the entrance to terrace floor	2	x	4	1.20		2.10	20.16	sq.mt		1	sq.mt	
6	Flooring with non-skid full body ceramic floor tiles of size 400mm x 400mm and thickness between 7 - 8mm 1st quality conforming to IS: 13711, IS: 13712, IS: 13630(Part 1 to 15) of any colour and finish in all shades and designs with borders and design as per the approved flooring pattern as directed by the Engineer-In -Charge, laying tiles using spacers of 2mm thick, set over base coat of cement mortar (1:8), 12mm thick using screened sand over CC bed already laid or RCC roof slab, including neat cement slurry of honey like consistency spread @ 3.3 Kgs per Sqm & jointed neatly with white cement paste to full depth mixed with pigment of matching shade, including cost of all materials like cement, screened sand, water and tiles etc., and overheads & contractors profit complete for finished item of work. (APSS No.701 & 707)												
	around cooler area at floor level	4	x	3	2.70	-	0.23	7.45	sq.mt		1	sq.mt	
	around the water point	4	x	3	2.70	-	0.23	7.45	sq.mt		1	sq.mt	
	to water point pedestal	4	x	4	0.23	-	0.70	2.58	sq.mt		1	sq.mt	
7	Supply and fixing of Ashirvad/ Ajay/ Astral Flowguard or equivalent CPVC Pipes and Fittings SDR 11 to meet the requirement of ASTM-D 2846 and are produced in CTS (Copper Tube Sizes 1/2" to 2") for hot and cold water (IS 15778:2007) including cost and conveyance of all materials to site, labour charges for fixing, overheads & contractors profit complete for finished item of work at all floor levels.												
	41.30mm OD pipe	4	x	1	25.00	-	-	100.00	Rmt		1	Rmt	
	Total												
8	Add 5% VAT									0.05			
9	TOTAL ESTIMATE COST												

