



RAJIV GANDHI UNIVERSITY OF KNOWLEDGE TECHNOLOGIES

(A.P Government Act 18 of 2008)

Nuzvid, RGUKT-campus, Krishna District, Andhra Pradesh-521202

Tele No: 08656-235557.

E-mail Id: ao.nuz@rgukt.in

Ref. No: RGUKT/NUZ/Proc/NIQ/Civil /Grill Door/17-18

Date: 30.05.2017

To

All Interested vendors

Dear Sir/ Madam,

SUB: NOTICE INVITING QUOTATION FOR REPARING WORKS- PROVIDING GRILL DOOR FACILITY IN HOSTELS AND ACADEMIC BLOCKS AT RGUKT – NUZVID.

The Administrative Officer, RGUKT- Nuzvid invites quotations for GRILL DOORS - Nuzvid, in Single bid as indicated, in sealed cover, is hereby invited to reach the undersigned on or before 08.06.2017. Kindly quote your lowest price including taxes & transportation.

The Details are as follows:-

1. Dismantling of wall
2. Providing of structural steel sections of TATA/VIZAG/JINDAL
3. Providing of enamel and emulsion paint of Asian/beger/sheenlac

@See enclosure

Please Note-

01. Address of the firms submitting the quotation and the Officer, to whom the quotation is addressed, must appear distinctly on the sealed cover as under. Quotation in must be sealed cover should reach or before 08.06.2017, by speed post/ Courier service/by person.
02. The following must be clearly written on the outer sealed cover irrespective of single bid. Without sealed cover, the quotation will not be accepted.

QUOTATION FOR EXECUTING OF CIVIL WORKS IN RGUKT- NUZVID

NIQ REF NO: RGUKT/NUZ/Proc/NIQ/CIVIL/GRILL DOOR/17-18 Date: 30.05.2017

To

The ADMINISTRATIVE OFFICER

RGUKT - NUZVID

KRISHNA (DIST) - A.P. - 521202

03. There is no Quotation document fee and Quotation document is to be downloaded from our website given below. www.rguktnuz.in/tenders or www.rguktn.ac.in/tenders
04. **Validity:** Quoted rates must valid for 120 days

05. **Delivery:** Unless otherwise stated delivery of goods at RGUKT-Nuzvid, will have to be maximum within 15days
 06. **Firm Registration Document and PAN Account No.** copy of the document to be furnished
 07. **CST/VAT/TIN No.** must appear in the Invoice/bill
 08. All aspects of safe delivery shall be the exclusive responsibility of the vendor
 09. **Late and delayed quotation:** Late and delayed tender will not be considered. In case any unscheduled holiday occurs on prescribed closing/opening date, the next working day shall be the prescribed date of closing/opening.
 10. **Bid not transferable:** The bid documents are not transferable and the seal and signature of the authorized official of the firm's must appear on all the papers and envelopes submitted.
 11. **Payment:** Payment will be made within 30 days from the date of successful delivery and acceptance of goods at RGUKT-Nuzvid, generally through RTGS / FUND TRANSFER. Following information must be clearly written in the quotation for RTGS / FUND TRANSFER:
 -
 - (a) Name of the Firm with complete postal address
 - (b) ACCOUNT No
 - (c) Name of the Bank with Branch where the Account exist
 - (d) IFSC CODE
 - (e) PAN No:
 12. Kindly read both the Instructions and Terms properly and see that instructions and terms are fully understood and complied. No correspondence shall be entertained in case your quotation is rejected on ground of not complying with our instructions, terms and conditions. In case of doubt please contact us at 08656- 235557 or the Administrative Office.
- 13. INSTRUCTION TO BIDDERS**
- A) Starting Date and Time: **30.05.2017**
 - (i) Last date & Time of receipt of Tender: **08.06.2017, (1700 HRS)**
 - (ii) Time of opening Tender: **09.06.2017, (1500 HRS)**
 - (iii) Venue of Bid opening: Office of the Administrative Officer's, RGUKT- Nuzvid.

Sd/-

Administrative Officer

DETAILED CUM ABSTRACT

FIXING OF STEEL DOORS IN THIRD FLOOR TO ACCESS THE TERRACE FLOOR AT RGUKT, NUZIVD

S.No.	Description of Item	Measurements						Contents	Unit	Rate	Per	Amount
		No.			L	B	D					
1	Dismantling, clearing away and carefully stacking useful materials for re-use and disposal of unserviceable materials with 100m lead as directed by Executive Engineer duly taking actual premeasurements before dismantling including all labour charges , overheads & contractor profit etc., complete											
a	For placing of anchor bolts in I-1	2	x	2	0.30	0.23	2.10	0.58	cum		1	cum
b	for placing of anchor bolts in I-2	2	x	2	0.30	0.23	2.10	0.58	cum		1	cum
c	For placing of anchor bolts in K-2	2	x	2	0.30	0.23	2.10	0.58	cum		1	cum
d	for placing of anchor bolts in K-3	2	x	2	0.30	0.23	2.10	0.58	cum		1	cum
e	For placing of anchor bolts in K-4	2	x	2	0.30	0.23	2.10	0.58	cum		1	cum
f	for placing of anchor bolts in Academic blocks	6	x	2	0.30	0.23	2.10	1.74	cum		1	cum
g	For shopping complex door	2	x	2	0.30	0.23	2.10	0.58	cum		1	cum
h	For making of grill partition(dismantling at bottom)	1	x	1	4.40	0.23	3.80	3.85	cum		1	cum
2	Providing Mild Steel structural steel Angles, Channels & I Sections of all sizes as per IS-1161, Labour charges for fabricating all steel works like angles, channels including cost of welding rods, power charges, etc excluding cost of fixing in position, for fixing iron grills, channels, flats erecting in position and fixing by using chain pulley blocks, Derek pole arrangements and cranes etc., complete in position INCLUDING ALL WASTAGES											
		no			L		Unit.wt					
a	for placing of outer frame with ISA 30x30x5mm	1	x	18	6.00	-	2.20	#####	kg		1	kg
b	for double door with ISA 30x30x5mm	2	x	18	5.10	-	2.20	#####	kg		1	kg
c	for placing of grill in horizontal direction with ISQA-16mm with 100mm c/c	36	x	22	0.45	-	2.00	#####	kg		1	kg
d	for placing of grill in vertical direction with ISQA-16mm with 10mm c/c	36	x	10	0.45	-	2.00	#####	kg		1	kg
e	For Making of aldrop and hook	1	x	36	1.00	-	2.20	79.20	kg		1	kg
f	For making of Grill partition frame in shopping complex outer frame ISA 30x30x5mm	1	x	1	16.40	-	2.20	36.08	kg		1	kg
g	For making of grill with ISQA 16mm with 100mm c/c	1	x	20	4.40	-	2.20	#####	kg		1	kg
		1	x	44	3.80	-	2.00	#####	kg		1	kg
3	Brick masonry for panel walls in superstructure with CM (1:5) prop: (Cement : Screened sand) using common burnt clay bricks of class as per Table- I of IS:1077-1992, Non- Modular or traditional size 23 x 11 x 7 cms from approved source having minimum crushing strength of 40 Kg/Sqcm. including cost and conveyance of all materials like cement, screened sand, bricks, water etc., to site, including sales & other taxes on all materials and such as labour charges, like mixing cement mortar, scaffolding charges, constructing masonry, lift charges, curing, etc.,and overheads & contractors profit complete for finished item of work. (APSS No. 501 & 504)											
a	For placing of anchor bolts in I-1	2	x	2	0.30	0.23	1.80	0.50	cum		1	cum
b	for placing of anchor bolts in I-2	2	x	2	0.30	0.23	1.80	0.50	cum		1	cum

c	For placing of anchor bolts in K-2	2	x	2	0.30	0.23	1.80	0.50	cum		1	cum				
d	for placing of anchor bolts in K-3	2	x	2	0.30	0.23	1.80	0.50	cum		1	cum				
e	For placing of anchor bolts in K-4	2	x	2	0.30	0.23	1.80	0.50	cum		1	cum				
f	for placing of anchor bolts in Academic blocks	6	x	2	0.30	0.23	1.80	1.49	cum		1	cum				
g	For shopping complex door	1	x	2	0.30	0.23	1.80	0.25	cum		1	cum				
4	Supply and placing of the Nominal Mix Concrete M 20 grade corresponding to IS 456 with minimum cement content of 225kgs per 1 cum of concrete using WEIGH BATCHER / MIXER with 20mm size graded machine crushed hard granite metal (coarse aggregate - as per IS 383 - 1970 and IS 2386 Part 1 to Part 8) from approved quarry including cost and conveyance of all materials like cement, fine aggregate (sand) coarse aggregate, water etc., to site and sales & other taxes on all materials, centering using Casurina Ballies, Bamboos, Wooden Reapers, Runners, Wood Posts, Wall Plates etc., including all operational, incidental and labour charges such as weigh batching, machine mixing, lifting of concrete manually, laying concrete, curing , overheads & contractors profit etc., complete but excluding cost of steel and its fabrication charges for finished item of work (APSS No. 402)															
a	For placing of anchor bolts in I-1	2	x	4	0.30	0.23	0.30	0.17	cum		1	cum				
b	for placing of anchor bolts in I-2	2	x	4	0.30	0.23	0.30	0.17	cum		1	cum				
c	For placing of anchor bolts in K-2	2	x	4	0.30	0.23	0.30	0.17	cum		1	cum				
d	for placing of anchor bolts in K-3	2	x	4	0.30	0.23	0.30	0.17	cum		1	cum				
e	For placing of anchor bolts in K-4	2	x	4	0.30	0.23	0.30	0.17	cum		1	cum				
f	for placing of anchor bolts in Academic blocks	6	x	4	0.30	0.23	0.30	0.50	cum		1	cum				
g	For shopping complex door	1	x	4	0.30	0.23	0.30	0.08	cum		1	cum				
h	For shopping complex partition(at bottom)	1	x	1	4.40	0.23	0.30	0.30	cum		1	cum				
5	Plastering 12mm thick single coat in CM(1:5) using screened sand including cost and conveyance of all materials like cement, sand, water etc., to site, including sales & other taxes on all materials, and all operational, incidental charges on materials and including cost of all labour charges for mixing mortar, finishing, curing as directed by Engineer-in-charge etc., and overheads & contractors profit complete for finished item of work.(SS 901,903 & 904)															
a	For placing of anchor bolts in I-1	2	x	4	0.30	-	2.10	5.04	sq.mt		1	sq.mt				
b	for placing of anchor bolts in I-2	2	x	4	0.30	-	2.10	5.04	sq.mt		1	sq.mt				
c	For placing of anchor bolts in K-2	2	x	4	0.30	-	2.10	5.04	sq.mt		1	sq.mt				
d	for placing of anchor bolts in K-3	2	x	4	0.30	-	2.10	5.04	sq.mt		1	sq.mt				
e	For placing of anchor bolts in K-4	2	x	4	0.30	-	2.10	5.04	sq.mt		1	sq.mt				
f	for placing of anchor bolts in Academic blocks	6	x	4	0.30	-	2.10	15.12	sq.mt		1	sq.mt				
g	For shopping complex door	1	x	4	0.30	-	2.10	2.52	sq.mt		1	sq.mt				
6	Supply & application of one coat water based cement primer of interior grade I and two coats of acrylic emulsion paint having VOC (Volatile Organic Compound) content less than 50 grams/litre for internal walls including cost and conveyance of all materials to site, sales & other taxes, incidental, operational and all labour charges etc., and overheads & contractors profit complete for finished item of work in all floors.															
a	For placing of anchor bolts in I-1	2	x	4	0.30	-	2.10	5.04	sq.mt		1	sq.mt				
b	for placing of anchor bolts in I-2	2	x	4	0.30	-	2.10	5.04	sq.mt		1	sq.mt				
c	For placing of anchor bolts in K-2	2	x	4	0.30	-	2.10	5.04	sq.mt		1	sq.mt				
d	for placing of anchor bolts in K-3	2	x	4	0.30	-	2.10	5.04	sq.mt		1	sq.mt				
e	For placing of anchor bolts in K-4	2	x	4	0.30	-	2.10	5.04	sq.mt		1	sq.mt				
f	for placing of anchor bolts in Academic blocks	6	x	4	0.30	-	2.10	15.12	sq.mt		1	sq.mt				

