



RAJIV GANDHI UNIVERSITY OF KNOWLEDGE TECHNOLOGIES

(A.P Government Act 18 of 2008)

Nuzvid, RGUKT-campus, Krishna District, Andhra Pradesh-521202

Tele No: 08656-235557.

E-mail Id: ao.nuz@rgukt.in

Ref. No: RGUKT/NUZ/Proc/NIQ/Civil /I-3 2nd & 3rd floor/17-18

Date: .05.2017

To

All Interested vendors

Dear Sir/ Madam,

SUB: NOTICE INVITING QUOTATION FOR REPARING WORKS- READINESS OF I-3 BLOCK 2nd & 3rd FLOOR RGUKT – NUZVID.

The Administrative Officer, RGUKT- Nuzvid invites quotations for READINESS OF I-3 BLOCK 2nd & 3rd FLOOR - RGUKT- Nuzvid, in Single bid as indicated, in sealed cover, is hereby invited to reach the undersigned on or before 08.06.2017. Kindly quote your lowest price including taxes & transportation.

The Details are as follows:-

1. Dismantling damaged floor
2. Replacement of ceramic floor tiles
3. Providing of 30mm thick shutter

@See enclosure

Please Note-

01. Address of the firms submitting the quotation and the Officer, to whom the quotation is addressed, must appear distinctly on the sealed cover as under. Quotation in must be sealed cover should reach or before 08.06.2017, by speed post/ Courier service/by person.
02. The following must be clearly written on the outer sealed cover irrespective of single bid. Without sealed cover, the quotation will not be accepted.

QUOTATION FOR EXECUTING OF CIVIL WORKS IN RGUKT- NUZVID

NIQ REF NO: RGUKT/NUZ/Proc/NIQ/CIVIL/I3-2nd & 3rd Floor/17-18 Date: 30.05.2017

To

The ADMINISTRATIVE OFFICER

RGUKT – NUZVID

KRISHNA (DIST) – A.P. – 521202

03. There is no Quotation document fee and Quotation document is to be downloaded from our website given below. www.rguktnuz.in/tenders or www.rguktn.ac.in/tenders

04. **Validity:** Quoted rates must valid for 120 days
05. **Delivery:** Unless otherwise stated delivery of goods at RGUKT-Nuzvid, will have to be maximum within 15days
06. **Firm Registration Document and PAN Account No.** copy of the document to be furnished
07. **CST/VAT/TIN No.** must appear in the Invoice/bill
08. All aspects of safe delivery shall be the exclusive responsibility of the vendor
09. **Late and delayed quotation:** Late and delayed tender will not be considered. In case any unscheduled holiday occurs on prescribed closing/opening date, the next working day shall be the prescribed date of closing/opening.
10. **Bid not transferable:** The bid documents are not transferable and the seal and signature of the authorized official of the firm's must appear on all the papers and envelopes submitted.
11. **Payment:** Payment will be made within 30 days from the date of successful delivery and acceptance of goods at RGUKT-Nuzvid, generally through RTGS / FUND TRANSFER. Following information must be clearly written in the quotation for RTGS / FUND TRANSFER: -
 - (a) Name of the Firm with complete postal address
 - (b) ACCOUNT No
 - (c) Name of the Bank with Branch where the Account exist
 - (d) IFSC CODE
 - (e) PAN No:
12. Kindly read both the Instructions and Terms properly and see that instructions and terms are fully understood and complied. No correspondence shall be entertained in case your quotation is rejected on ground of not complying with our instructions, terms and conditions. In case of doubt please contact us at 08656- 235557 or the Administrative Office.

13. INSTRUCTION TO BIDDERS

- A) Starting Date and Time: **30.05.2017**
 - (i) Last date & Time of receipt of Tender: **08.06.2017, (1700 HRS)**
 - (ii) Time of opening Tender: **09.06.2017, (1500 HRS)**
 - (iii) Venue of Bid opening: Office of the Administrative Officer's, RGUKT- Nuzvid.

Sd/-

Administrative Officer

DETAILED CUM ABSTRACT

READINESS OF I-3 BLOCK 2ND AND 3RD FLOORS TO PROVIDE THE ACCOMMODATION

S.No.	Description of Item	Measurements						Contents	Unit	Rate	Per	Amount
		No.		L	B	D						
1	Dismantling, clearing away and carefully stacking useful materials for re-use and disposal of unserviceable materials with 100m lead as directed by Executive Engineer duly taking actual premeasurements before dismantling including all labour charges , overheads & contractor profit etc., complete											
	damaged floor tiles in 2nd floor	1	x	645	0.40	0.40	-	103.20	sq.mt		1	sq.mt
	for dismantling of false ceiling	1	x	150	0.40	0.40	-	24.00	sq.mt		1	sq.mt
2	Flooring with non-skid full body ceramic floor tiles of size 400mm x 400mm and thickness between 7 - 8mm 1st quality conforming to IS: 13711, IS: 13712, IS: 13630(Part 1 to 15) of any colour and finish in all shades and designs with borders and design as per the approved flooring pattern as directed by the Engineer-In -Charge, laying tiles using spacers of 2mm thick, set over base coat of cement mortar (1:8), 12mm thick using screened sand over CC bed already laid or RCC roof slab, including neat cement slurry of honey like consistency spread @ 3.3 Kgs per Sqm & jointed neatly with white cement paste to full depth mixed with pigment of matching shade, including cost of all materials like cement, screened sand , water and tiles etc., and overheads & contractors profit complete for finished item of work. (APSS No.701 & 707)											
	damaged floor tiles in 2nd floor	1	x	645	0.40	0.40	-	103.20	sq.mt		1	sq.mt
	for dismantling of false ceiling	1	x	150	0.40	0.40	-	24.00	sq.mt		1	sq.mt
3	Supply and fixing doors as per drawings with medium teak wood frame of section 100mm x 65 mm and ISI marked flush door shutters of 30 mm thick single shutter with bond wood solid block board type Core having cross bands and face veneers, hot pressed bonded with water proof phenol formaldehyde synthetic resin factory made conforming to IS 2202-1991 (Part-I) both sides commercial ply with internal lipping on all sides including cost and conveyance to site of teak wood frame, flush shutter including supply and fixing 6 Nos. MS Z hold fasts of size 300 mm x 40 mm x 5mm including cost of ISI marked MS powder coated fixtures of 3 Nos. butt hinges (IS:205) 150mm long, 1 No. aldrop (IS:2681) 300mm long, 1 No. tower bolt (IS:204) of 200 mm x 10 mm dia at top, 2 Nos. 150 mm long handles (IS:208), 1 No. door stopper and 1 No. rubber bush including fixing the fixtures to door with required number of screws, bolt and nuts including labour charges for fixing the frame in position, fixing the shutter to the frame etc, including overheads & contractors profit complete for finished item of work as per APSS 1001 & 1002 (The vertical frame of door shall be embedded in flooring for a depth of not less than 10 mm) (900mm x 2100mm)											
	replacment of damaged door only	1	x	5	1.10	-	1.20	6.60	sq.mt		1	sq.mt
4	Polishing two coats to teak wood doors using French spirit polish of approved brand for new wood work to teak wood frame and shutters including sand papering to smooth surfaces etc. including cost and conveyance of all materials to site, all labour charges etc., complete for finished item of work in all floors.											
	for door front face	1	x	5	1.10	-	1.20	6.60	sq.mt		1	sq.mt

