



RAJIV GANDHI UNIVERSITY OF KNOWLEDGE TECHNOLOGIES

(A.P Government Act 18 of 2008)

RGUKT- Nuzvid Institute, Krishna District, Andhra Pradesh-521202

RGUKT

Tele No: 08656-235557

E-mail Id: ao.nuz@rgukt.in

LT No: RGUKT/NUZ/Proc/Civil/Carpentry/ Doors & Frames/2017-18

Date: 09.11.2017

Limited Tender

To

All Interested vendors

Dear Sir/ Madam,

Sealed tenders are invited from registered Civil Contractors for execution carpentry work (Replacement of doors and frame in new campus kitchen and dining halls) with the following LT specifications along with terms and conditions details given here under.

1	Name of the Work	Civil Works (Carpentry Work) in RGUKT – Nuzvid
2	Availability of Tender Document	Tender document to be downloaded from website: www.rguktn.ac.in from 09.11.2017 to 22.11.2017.
3	Cost of Tender Document	Rs. 200.00 (Non Refundable), in the shape of a bank draft/banker's and in favor of the Director, RGUKT, payable at Nuzvid.
4	Last date for submission of Tender Documents	22.11.2017, upto :4:00 PM, Tender Box available at Administrative Office, I-3 building, RGUKT- Nuzvid
5	Opening of Tender	23.11.17 at 11:30 AM in Administrative Officer's room, I -3 Building, RGUKT- Nuzvid.
7	Performance security(PS)	Rs. 30,000 (Refundable), in the shape of a bank draft/banker's and in favor of the Director, RGUKT, payable at Nuzvid. The amount will be refunded within 30days after completion of liability period and satisfactory certificate from the engg. section
8	Liability Period	3 months
9	Payment Terms	100% payment within 30days from the date of satisfactory receipt installation and acceptance of equipment.
10	Completion of the work	25 days from Work Order

General Terms & Conditions:-

1. Quoting merely the lowest price does not confer any right to any bidder for award of supply order. The Institute Purchase Committee, reserves the right to select the equipment any bid under the grounds of specification compliance, technologically advanced quality, proven performance track record, brand reputation, offer of additional / special features, Compatibility with the existing System, etc.
2. The Quotation/Tender Document Fee and PS should be submitted along with your quotations in a separate envelop.
3. The unsuccessful tenderer PS (Performance Security) shall be returned after issuing of Work order

4. The Tender (separate envelopes for technical and commercial bids with labeling) must be submitted sealed cover, superscribing **“Tender for replacement of doors +frames in Kitchen cum Dining hall.** The name and address of the bidder should also be mentioned at the “From address” space.
5. Address of the Contractors submitting the quotation/tender and the Officer, to whom the quotation/tender is addressed, must appear distinctly on the sealed cover as under. Quotation/Tender in must be sealed cover should reach or before 22.11.2017, upto 4 PM by Courier service/Speed Post/Registered Post/ by person.
6. Tenders will not be accepted through fax / e-mail.
7. The Tender/quotation must accompany Performance security (PS), which is refundable after within 30days after completion of liability period and submission of satisfactory certificate from the Engg. Section, in the shape of a bank draft/banker’s cheque.
8. Vendors are requested to consider maximum discount that can be given to an educational institution.
9. The bidder should posses a GST Registration issued by Sales Tax department of any Indian State/Union Territory.
10. PAN No. Should be provided in the quotation along with the terms and conditions of delivery.
11. Payment will be made only after delivery and successful installation.
12. The tenderer has to submit a copy of their registration certificates.
13. Date of opening of quotation will be notified on the last date of submission. Representatives of the agencies may attend the Quotation Opening Meeting.
14. The taxes / duties / discounts, if applicable, are to be explicitly and separately shown in the bid.
15. RGUKT- Nuzvid reserves the right to accept or reject any or all tenders without assigning any reason whatever it may be.
16. Intending Tenderer shall visit the RGUKT, Nuzvid campus to acquaint with local site conditions, nature and requirement of work, present conditions of Premises/fittings/fixtures/material etc., and make assessment of labour and material, etc. required before quoting for the Tender
17. The incomplete tenders are liable to reject without assigning any reason.
18. If any additional charges related to taxes should be mentioned separately or otherwise the total amount will be treated as all inclusive.
19. During course of contract all the issues relating financial matters, manpower matters, material matters and any risk to the workers and in any manner are related to the tenderer only, in the connection RGUKT, Nuzvid is no way concern.
20. **Wherever there is a discrepancy in the quoted figures and words, the amount quoted in words will be taken as final.**
21. **Wherever there is an over writing, the correction should be duly initialed.**
22. **Eligibility Criteria:**
23. The contractor must have the requisite domain expertise with regard to Provide Civil Work services of the work they are quoting.
24. **Bid Validity:** The validity period of the tenders shall be minimum 180 (one hundred eighty) days from the end date of submission of bid.
25. **Specifications details are to be submitted along with Tender documents.**
26. **The Contractor should sign in all papers of the Tender document.**
27. **The quotation without Tender fee and PS will be treated as invalid**

Bill of Quantities

REPLACEMENT OF DOORS AND FRAME IN NEW CAMPUS KITCHEN AND DINING HALLS

S.No	Description of Item	Measurements				Conte nts	Unit	Rate	Per	Amount	
		No.	L	B	D						
1	Supply and fixing doors as per drawings with medium teak wood frame of section 100mm x 65 mm and ISI marked flush door shutters of 30 mm thick double shutters with bond wood solid block board type Core having cross bands and face veneers, hot pressed bonded with water proof phenol formaldehyde synthetic resin factory made conforming to IS 2202-1991 (Part-I) both sides commercial ply with internal lipping on all sides including cost and conveyance to site of teak wood frame, flush shutter including supply and fixing 6 Nos. MS Z hold fasts of size 300 mm x 40 mm x 5mm including cost of ISI marked MS powder coated fixtures of 6 Nos. butt hinges (IS:205)150mm long, 1 No. aldrop (IS:2681) 300mm long, 2 Nos. tower bolts (IS:204) of 200 mm x 10 mm dia at top, 2 Nos. 150 mm long handles (IS:208), 2 Nos. door stoppers and 2 Nos. rubber bushes including fixing the fixtures to door with required number of screws, bolt and nuts including labour charges for fixing the frame in position, fixing the shutter to the frame etc, including overheads & contractors profit complete for finished item of work as per APSS 1001 & 1002 (The vertical frame of door shall be embedded in flooring for a depth of not less than 10 mm) (1800mm x 2100mm)										
	Door + Frame										
	in D-1 hall main entrance	1	x	2	1.80	-	2.10	7.56	Sq.m t	1	Sq. mt
	in D-2 hall main entrance	1	x	1	1.80	-	2.10	3.78	Sq.m t	1	Sq. mt
	in D-3 hall main entrance	1	x	1	1.80	-	2.10	3.78	Sq.m t	1	Sq. mt
	in D-4 hall main entrance	1	x	2	1.80	-	2.10	7.56	Sq.m t	1	Sq. mt
	Frame only										
	in D-3 hall main entrance	1	x	1	1.80	-	2.10	3.78	Sq.m t	1	Sq. mt
2	Supply and fixing doors as per drawings with medium teak wood frame of section 100mm x 65 mm and ISI marked flush door shutters of 30 mm thick double shutters with bond wood solid block board type Core having cross bands and face veneers, hot pressed bonded with water proof phenol formaldehyde synthetic resin factory made conforming to IS 2202-1991 (Part-I) both sides commercial ply with internal lipping on all sides including cost and conveyance to site of teak wood frame, flush shutter including supply and fixing 6 Nos. MS Z hold fasts of size 300 mm x 40 mm x 5mm including cost of ISI marked MS powder coated fixtures of 6 Nos. butt hinges (IS:205) 150mm long, 1 No. aldrop (IS:2681) 300mm long, 2 Nos. tower bolts (IS:204) of 200 mm x 10 mm dia at top, 2 Nos. 150 mm long handles (IS:208), 2 Nos. door stoppers and 2 Nos. rubber bushes including fixing the fixtures to door with required number of screws, bolt and nuts including labour charges for fixing the frame in position, fixing the shutter to the frame etc., including overheads & contractors profit complete for finished item of work as per APSS 1001 & 1002 (The vertical frame of door shall be embedded in flooring for a depth of not less than 10 mm) (1200mm x 2100mm)										
	Door + Frame										
	in D-2 hall store	1	x	1	1.20	-	2.10	2.52	sq.m	1	sq. m
	in D-3 hall hand wash area	1	x	2	1.20	-	2.10	5.04	sq.m	1	sq. m
	Door only										
	in D-1 hall hand wash area	1	x	1	1.20	-	2.10	2.52	sq.m	1	sq. m
	in D-3 hall hand wash area	1	x	2	1.20	-	2.10	5.04	sq.m	1	sq. m
3	Dismantling, clearing away and carefully stacking useful materials for re-use and disposal of unserviceable materials with 100m lead as directed by Executive Engineer duly taking actual premeasurements before dismantling including all labour charges , overheads & contractor profit etc., complete										
	Door + Frame										
	in D-1 hall main entrance	1	x	2	0.30	0.23	2.10	0.29	Sq.m t	1	Sq. mt

	in D-2 hall main entrance	1	x	1	0.30	0.23	2.10	0.14	Sq.m t		1	Sq. mt	
	in D-3 hall main entrance	1	x	1	0.30	0.23	2.10	0.14	Sq.m t		1	Sq. mt	
	in D-4 hall main entrance	1	x	2	0.30	0.23	2.10	0.29	Sq.m t		1	Sq. mt	
	Door + Frame												
	in D-2 hall store	1	x	1	0.30	0.23	2.10	0.14	sq.m		1	sq. m	
	in D-3 hall hand wash area	1	x	2	0.30	0.23	2.10	0.29	sq.m		1	sq. m	
4	Brick masonry for panel walls in superstructure with CM (1:5) prop: (Cement : Sand) using common burnt clay bricks of class as per Table- I of IS:1077-1992, Non- Modular or traditional size 23 x 11 x 7 cms from approved source having minimum crushing strength of 40 Kg/Sqcm. including cost and conveyance of all materials like cement, screened sand, bricks, water etc., to site, including sales & other taxes on all materials and such as labour charges, like mixing cement mortar, scaffolding charges, constructing masonry, lift charges, curing, etc.,and overheads & contractors profit complete for finished item of work. (APSS No. 501 & 504).												
	Door + Frame												
	in D-1 hall main entrance	1	x	2	0.30	0.23	2.10	0.29	Sq.m t		1	Sq. mt	
	in D-2 hall main entrance	1	x	1	0.30	0.23	2.10	0.14	Sq.m t		1	Sq. mt	
	in D-3 hall main entrance	1	x	1	0.30	0.23	2.10	0.14	Sq.m t		1	Sq. mt	
	in D-4 hall main entrance	1	x	2	0.30	0.23	2.10	0.29	Sq.m t		1	Sq. mt	
	Door + Frame												
	in D-2 hall store	1	x	1	0.30	0.23	2.10	0.14	sq.m		1	sq. m	
	in D-3 hall hand wash area	1	x	2	0.30	0.23	2.10	0.29	sq.m		1	sq. m	
5	Plastering 12mm thick single coat in CM(1:5) using screened sand including cost and conveyance of all materials like cement, sand, water etc., to site, including sales & other taxes on all materials, and all operational, incidental charges on materials and including cost of all labour charges for mixing mortar, finishing, curing as directed by Engineer-in-charge etc., and overheads & contractors profit complete for finished item of work.(SS 901,903 & 904)												
	Door + Frame												
	in D-1 hall main entrance	4	x	2	0.30	-	2.10	5.04	Sq.m t		1	Sq. mt	
	in D-2 hall main entrance	4	x	1	0.30	-	2.10	2.52	Sq.m t		1	Sq. mt	
	in D-3 hall main entrance	4	x	1	0.30	-	2.10	2.52	Sq.m t		1	Sq. mt	
	in D-4 hall main entrance	4	x	2	0.30	-	2.10	5.04	Sq.m t		1	Sq. mt	
	Door + Frame												
	in D-2 hall store	4	x	1	0.30	-	2.10	2.52	sq.m		1	sq. m	
	in D-3 hall hand wash area	4	x	2	0.30	-	2.10	5.04	sq.m		1	sq. m	
6	Painting to new wood work and flush shutters with lappam finish , over a primary coat and painting two coats of synthetic enamel paint Grade-I VOC (Volatile Organic Compound) content less than 50 grams/litre of approved shade including cost and conveyance of all materials to site cost of primer coat and all labour charges etc. complete including applying sand paper on lappam coats for neat finish including sales & other taxes on cost of all materials etc., and overheads & contractors profit complete in all floors (APSS No.1200, 1207 & 1211).												
	Door + Frame				L	Coefficient							
	in D-1 hall main entrance	1	x	2	1.80	1.20	2.10	9.07	Sq.m t		1	Sq. mt	
	in D-2 hall main entrance	1	x	1	1.80	1.20	2.10	4.54	Sq.m t		1	Sq. mt	

	in D-3 hall main entrance	1	x	1	1.80	1.20	2.10	4.54	Sq.m t		1	Sq. mt	
	in D-4 hall main entrance	1	x	2	1.80	1.20	2.10	9.07	Sq.m t		1	Sq. mt	
	Frame only												
	in D-3 hall main entrance	1	x	1	1.80	1.20	2.10	4.54	Sq.m t		1	Sq. mt	
	Door + Frame												
	in D-2 hall store	1	x	1	1.20	1.20	2.10	3.02	sq.m		1	sq. m	
	in D-3 hall hand wash area	1	x	2	1.20	1.20	2.10	6.05	sq.m		1	sq. m	
	Door only												
	in D-1 hall hand wash area	1	x	1	1.20	1.20	2.10	3.02	sq.m		1	sq. m	
	in D-3 hall hand wash area	1	x	2	1.20	1.20	2.10	6.05	sq.m		1	sq. m	
7	Providing dadoing to walls with glazed full body ceramic tiles of any size and thickness between 5 to 7mm 1st quality conforming to IS: 13711, IS: 13712, IS: 13630(Parts 1 to 15) of any colour and finish in all shades and designs with borders as approved by Engineer-in-Charge set over base coat of CM(1:5) 12 mm thick using screened sand with cement slurry of honey like consistency spread at the rate of 3.30 kgs per sqm and jointing with white cement paste mixed with pigment of matching shade to full depth, including cost of all materials like tiles, cement, sand and water etc., and overheads & contractors profit complete for finished item of work.												
	Door + Frame												
	in D-2 hall store	2	x	1	0.30	-	2.10	1.26	sq.m		1	sq. m	
	in D-3 hall hand wash area	2	x	2	0.30	-	2.10	2.52	sq.m		1	sq. m	
8	Supply & application of one coat water based cement primer of interior grade I and two coats of acrylic emulsion paint having VOC (Volatile Organic Compound) content less than 50 grams/litre for internal walls including cost and conveyance of all materials to site, sales & other taxes, incidental, operational and all labour charges etc., and overheads & contractors profit complete for finished item of work in all floors.												
	in D-1 hall main entrance	4	x	2	0.30	-	2.10	5.04	Sq.m t		1	Sq. mt	
	in D-2 hall main entrance	4	x	1	0.30	-	2.10	2.52	Sq.m t		1	Sq. mt	
	in D-3 hall main entrance	4	x	1	0.30	-	2.10	2.52	Sq.m t		1	Sq. mt	
	in D-4 hall main entrance	4	x	2	0.30	-	2.10	5.04	Sq.m t		1	Sq. mt	
	Frame only												
	in D-3 hall main entrance	4	x	1	0.30	-	2.10	2.52	Sq.m t		1	Sq. mt	
	Door + Frame												
	in D-2 hall store	4	x	1	0.30	-	2.10	2.52	Sq.m t		1	Sq. mt	
	in D-3 hall hand wash area	4	x	2	0.30	-	2.10	5.04	Sq.m t		1	Sq. mt	
9	Polishing two coats to teak wood doors using French spirit polish of approved brand for new wood work to teak wood frame and shutters including sand papering to smooth surfaces etc. including cost and conveyance of all materials to site, all labour charges etc., complete for finished item of work in all floors.												
	to existing all main doors	1	x	30	1.80	1.20	2.10	136.08	sq.m t		1	sq. mt	
	to existing wash area doors	1	x	5	1.20	1.20	2.10	15.12	sq.m t		1	sq. mt	

10	Painting to old wood work and flush shutters with two coats of synthetic enamel paint Grade-II VOC (Volatile Organic Compound) content less than 50 grams/litre of approved brand and shade including cost and conveyance of all materials to site and all labour charges etc. complete, sales & other taxes on cost of all materials etc.and overheads & contractors profit complete in all floors (APSS No.1200, 1207 & 1211) .												
	to existing doors	1	x	13	0.75	1.20	2.10	24.57	sq.m t		1	sq. mt	
TOTAL													
GST@....													
TOTAL COST													

Sd/-
Administrative Officer