



RAJIV GANDHI UNIVERSITY OF KNOWLEDGE TECHNOLOGIES
(A.P Government Act 18 of 2008)

Nuzvid, RGUKT-campus, Krishna District, Andhra Pradesh-521202

Tele No: 08656-235557.

E-mail Id: ao.nuz@rgukt.in

Ref. No: RGUKT/NUZ/Proc/NIQ/Civil/Academic Blocks/FT/18-19/

Date:09.10.2018

To

All Interested vendors

Dear Sir/ Madam,

SUB: NOTICE INVITING QUOTATION FOR REPARING WORKS- Replace the damaged floor Tiles in Academic Blocks - RGUKT – NUZVID.

The Administrative Officer, RGUKT- Nuzvid invites quotations for Civil works (Replace the damaged floor Tiles in Academic Blocks) RGUKT- Nuzvid, in Single bid as indicated, in sealed cover, is hereby invited to reach the undersigned on or before 22.10.2018. Kindly quote your lowest price including GST, Labour & transportation.

The Details are as follows:-

& See enclosure

Please Note-

01. The following must be clearly written on the outer sealed cover irrespective of single bid. Without sealed cover, the quotation will not be accepted.

QUOTATION FOR EXECUTING OF CIVIL WORKS IN RGUKT- NUZVID

NIQ REF NO: RGUKT/NUZ/Proc/NIQ/CIVIL/Academic Blocks/FT/18-19 Date:09.10.2018

To

The ADMINISTRATIVE OFFICER

RGUKT – NUZVID

KRISHNA (DIST) – A.P. – 521202

02. There is no Quotation document fee and Quotation document is to be downloaded from our website given below. www.rguktnuz.in/tenders or www.rguktn.ac.in/tenders
03. **Validity:** Quoted rates must valid for 120 days
04. **Delivery:** Unless otherwise stated delivery of goods at RGUKT-Nuzvid, will have to be maximum within 15days
05. **Firm Registration Document and PAN Account No.** copy of the document to be furnished
06. **GST No.** must appear in the Invoice/bill
07. All aspects of safe delivery shall be the exclusive responsibility of the vendor

08. **Late and delayed quotation:** Late and delayed tender will not be considered. In case any unscheduled holiday occurs on prescribed closing/opening date, the next working day shall be the prescribed date of closing/opening.
09. **Bid not transferable:** The bid documents are not transferable and the seal and signature of the authorized official of the firm's must appear on all the papers and envelopes submitted.
10. **Payment:** Payment will be made within 30 days from the date of successful delivery and acceptance of goods at RGUKT-Nuzvid, generally through RTGS / FUND TRANSFER. Following information must be clearly written in the quotation for RTGS / FUND TRANSFER: -
- (a) Name of the Firm with complete postal address
 - (b) ACCOUNT No
 - (c) Name of the Bank with Branch where the Account exist
 - (d) IFSC CODE
 - (e) PAN No:
11. Kindly read both the Instructions and Terms properly and see that instructions and terms are fully understood and complied. No correspondence shall be entertained in case your quotation is rejected on ground of not complying with our instructions, terms and conditions. In case of doubt please contact us at 8333981200 or the Administrative Office.

12. INSTRUCTION TO BIDDERS

A) Important Date and Time:

(i) Last date & Time of receipt of Tender: **22.10.2018, (1700 HRS)**

(ii) Time of opening Tender: **23.10.2018, (1500 HRS)**

(iii) Venue of Bid opening: Office of the Administrative Officer's, RGUKT- Nuzvid.

Sd/-

Administrative Officer

Price Bid:

REPLACEMENT OF DAMAGED FLOOR TILES IN ACADEMIC BLOCK												
S.No.	Description of Item	Measurements						Contents	Unit	Rate	Per	Amount
		No.		L	B	D						
1	Dismantling, clearing away and carefully stacking useful materials for re-use and disposal of unserviceable materials with 100m lead as directed by Executive Engineer duly taking actual premeasurements before dismantling including all labour charges , overheads & contractor profit etc., complete											
	A-2 block - Ground floor	1	x	76	0.40	0.40	0.06	0.73				
	A-2 block - First floor	1	x	22	0.40	0.40	0.06	0.21				
	A-2 block - Second floor	1	x	3	0.40	0.40	0.06	0.03				
	A-2 block - Third floor	1	x	140	0.40	0.40	0.06	1.34				
	A-3 block - Ground floor	1	x	97	0.40	0.40	0.06	0.93				
	A-3 block - First floor	1	x	45	0.40	0.40	0.06	0.43				
	A-3 block - Second floor	1	x	64	0.40	0.40	0.06	0.61				
	A-3 block - Third floor	1	x	57	0.40	0.40	0.06	0.55				
	A-4 block - Ground floor	1	x	167	0.40	0.40	0.06	1.60				
	A-4 block - First floor	1	x	54	0.40	0.40	0.06	0.52				
	A-4 block - Second floor	1	x	106	0.40	0.40	0.06	1.02				
	A-4 block - Third floor	1	x	219	0.40	0.40	0.06	2.10				
								10.07	cum	1	cum	
2	Plain Cement Concrete (1:4:8) (cement: fine aggregate: Coarse aggregate) for foundations and under flooring bed using coarse aggregate 20mm size hard, machine crushed granite from approved quarry including cost and conveyance of all materials like cement, sand, coarse aggregate, water etc. to site, including sales & other taxes on all materials and including all charges for machine mixing, laying concrete in foundations and under flooring bed, ramming in 15 cm layers finishing top surface to the required level curing etc., and overheads & contractors profit complete for finished item of work. (APSS No. 402)											
	A-2 block - Ground floor	1	x	50	0.40	0.40	0.06	0.48				
	A-2 block - First floor	1	x	21	0.40	0.40	0.06	0.20				
	A-2 block - Second floor	1	x	1	0.40	0.40	0.06	0.01				
	A-2 block - Third floor	1	x	128	0.40	0.40	0.06	1.23				
	A-3 block - Ground floor	1	x	39	0.40	0.40	0.06	0.37				
	A-3 block - First floor	1	x	36	0.40	0.40	0.06	0.35				
	A-3 block - Second floor	1	x	44	0.40	0.40	0.06	0.42				
	A-3 block - Third floor	1	x	39	0.40	0.40	0.06	0.37				
	A-4 block - Ground floor	1	x	98	0.40	0.40	0.06	0.94				
	A-4 block - First floor	1	x	50	0.40	0.40	0.06	0.48				
	A-4 block - Second floor	1	x	83	0.40	0.40	0.06	0.80				
	A-4 block - Third floor	1	x	96	0.40	0.40	0.06	0.92				
								6.57	cum	1	cum	

3	Flooring with non-skid full body ceramic floor tiles of size 400mm x 400mm and thickness between 7 - 8mm 1st quality conforming to IS: 13711, IS: 13712, IS: 13630(Part 1 to 15) of any colour and finish in all shades and designs with borders and design as per the approved flooring pattern as directed by the Engineer-In -Charge, laying tiles using spacers of 2mm thick, set over base coat of cement mortar (1:8), 12mm thick using screened sand over CC bed already laid or RCC roof slab, including neat cement slurry of honey like consistency spread @ 3.3 Kgs per Sqm & jointed neatly with white cement paste to full depth mixed with pigment of matching shade, including cost of all materials like cement, screened sand , water and tiles etc., and overheads & contractors profit complete for finished item of work. (APSS No.701 & 707)										
	A-2 block - Ground floor	1	x	50	0.40	0.40	-	8.00			
	A-2 block - First floor	1	x	21	0.40	0.40	-	3.36			
	A-2 block - Second floor	1	x	1	0.40	0.40	-	0.16			
	A-2 block - Third floor	1	x	128	0.40	0.40	-	20.48			
	A-3 block - Ground floor	1	x	39	0.40	0.40	-	6.24			
	A-3 block - First floor	1	x	36	0.40	0.40	-	5.76			
	A-3 block - Second floor	1	x	44	0.40	0.40	-	7.04			
	A-3 block - Third floor	1	x	39	0.40	0.40	-	6.24			
	A-4 block - Ground floor	1	x	98	0.40	0.40	-	15.68			
	A-4 block - First floor	1	x	50	0.40	0.40	-	8.00			
	A-4 block - Second floor	1	x	83	0.40	0.40	-	13.28			
	A-4 block - Third floor	1	x	96	0.40	0.40	-	15.36			
								109.60	Sq.mt	1	Sq.mt
4	Providing skirting to internal walls with non-skid red or white full body ceramic floor tiles of thickness between 7-8 mm 1st quality of any colour and finish in all shades and designs as approved by Engineer-in-charge, length equal to flooring tiles, set over base coat of CM(1:5) 12 mm thick using screened sand with cement slurry of honey like consistency spread at the rate of 3.30 kgs per sqm and jointing with white cement paste mixed with pigment of matching shade to full depth, including cost of all materials like tiles, cement, sand and water, overheads & contractors profit complete for finished item of work.(APSS No.701 &707)										
	A-2 block - Ground floor	1	x	26	0.40	-	-	10.40			
	A-2 block - First floor	1	x	1	0.40	-	-	0.40			
	A-2 block - Second floor	1	x	2	0.40	-	-	0.80			
	A-2 block - Third floor	1	x	13	0.40	-	-	5.20			
	A-3 block - Ground floor	1	x	58	0.40	-	-	23.20			
	A-3 block - First floor	1	x	9	0.40	-	-	3.60			
	A-3 block - Second floor	1	x	20	0.40	-	-	8.00			
	A-3 block - Third floor	1	x	18	0.40	-	-	7.20			
	A-4 block - Ground floor	1	x	69	0.40	-	-	27.60			
	A-4 block - First floor	1	x	4	0.40	-	-	1.60			
	A-4 block - Second floor	1	x	23	0.40	-	-	9.20			
	A-4 block - Third floor	1	x	123	0.40	-	-	49.20			
								146.40	Rmt	1	Rmt
5	Total										
6	Add GST										
7	Total Estimated Cost										

Authorized Signature & Stamp