



RAJIV GANDHI UNIVERSITY OF KNOWLEDGE TECHNOLOGIES

(A.P Government Act 18 of 2008)

Nuzvid, RGUKT-campus, Krishna District, Andhra Pradesh-521202

Tele No: 08656-235557.

E-mail Id: ao.nuz@rgukt.in

Ref. No: RGUKT/NUZ/Proc/NIQ/Civil /Transformer yards/painting/18-19

Date:01.11.2018

To

All Interested vendors

Dear Sir/ Madam,

SUB: NOTICE INVITING QUOTATION FOR EXECUTION WORKS- PROVIDING OF PAINTING WORKS TO TRANSFORMER YARDS AND SUBSTATIONS AT RGUKT – NUZVID.

Technical Bid

The Administrative Officer, RGUKT- Nuzvid invites quotations for Painting works to Transformer yards and substations at - RGUKT- Nuzvid, in Single bid as indicated, in sealed cover. Kindly quote your lowest price including labour charges, taxes & transportation.

The Details are as follows:-

Please Note-

01. The following must be clearly written on the outer sealed cover irrespective of single bid. Without sealed cover, the quotation will not be accepted.

QUOTATION FOR EXECUTING OF PAINTING WORKS IN RGUKT- NUZVID

NIQREF NO:RGUKT/NUZ/Proc/NIQ/CIVIL/PAINTING WORKS/18-19 Date: 01. 11.2018

To

The ADMINISTRATIVE OFFICER

RGUKT – NUZVID

KRISHNA (DIST) – A.P. – 521202

02. There is no Quotation document fee and Quotation document is to be downloaded from our website given below. www.rguktnuz.in/tenders or www.rguktn.ac.in/tenders
03. **Validity:** Quoted rates must valid for 120 days
04. **Delivery:** Unless otherwise stated delivery of goods at RGUKT-Nuzvid, will have to be maximum within **20days**
05. **Firm Registration Document and PAN Account No.** copy of the document to be furnished
06. **GST.No** must appear in the Invoice/Bill
07. All aspects of safe delivery shall be the exclusive responsibility of the vendor

08. **Late and delayed quotation:** Late and delayed tender will not be considered. In case any unscheduled holiday occurs on prescribed closing/opening date, the next working day shall be the prescribed date of closing/opening.
09. **Bid not transferable:** The bid documents are not transferable and the seal and signature of the authorized official of the firm's must appear on all the papers and envelopes submitted.
01. **Payment:** Payment will be made within 30 days from the billing date after getting satisfaction certificate from the concerned department. Payment would be made through online mode only: -
- (a) Name of the Firm with complete postal address
 - (b) ACCOUNT No
 - (c) Name of the Bank with Branch where the Account exist
 - (d) IFSC CODE
 - (e) PAN No:
02. Kindly read both the Instructions and **Terms & conditions** properly and see that instructions and terms are fully understood and complied. No correspondence/communication shall be entertained in case your quotation is rejected on ground of not complying with our instructions, terms and conditions. **For any clarifications please contact us at 8333981200.**
03. **The contractor/bidder should quote the price bid in percentage on overall tender value.**
04. **No modification/deviations admissible in price bid and Technical bid**
- 05. INSTRUCTION TO BIDDERS**
- (i) Last date & Time of receipt of Tender: **15.11.2018, (1700 HRS)**
 - (ii) Time of opening Tender: **16.11.2018, (1500 HRS)**
 - (iii) Venue of Bid opening: Office of the Administrative Officer's, RGUKT- Nuzvid.

Sd/-

Administrative Officer

Bill of quantities

PAINTING WORK TO TRANSFORMER AND SUB STATION YARDS AT RGUKT-IIIT NUZVID

S.No.	Description of Item	Measurements						Contents	Unit	Rate	Per	Amount	
		No.		L	B	D	Coefficient						
1	Painting two coats with synthetic enamel paint Grade-II VOC (Volatile Organic Compound) content less than 50 grams/litre over primer coat of red oxide to new iron work including cost and conveyance of all materials to site, sales & other taxes, incidental, operational and all labour charges etc., and overheads & contractors profit complete for finished item of work in all floors. (SS No. 1201, 1212 & 1207).												
1.1	for pillar at M-1 quarters	1	x	6	1.25	1.50	2.20	24.75					
		1	x	4	0.75	1.50	2.20	9.90					
1.2	Pillar at N-2 quarters	1	x	6	1.25	1.50	2.20	24.75					
		1	x	4	0.75	1.50	2.20	9.90					
1.3	Pillar at N-4 quarters	1	x	6	1.25	1.50	2.20	24.75					
		1	x	4	0.75	1.50	2.20	9.90					
1.4	Pillar at Q-3 quarters	1	x	6	1.25	1.50	2.20	24.75					
		1	x	4	0.75	1.50	2.20	9.90					
1.5	Pillar at P-2 quarters	1	x	6	1.25	1.50	2.20	24.75					
		1	x	4	0.75	1.50	2.20	9.90					
1.6	Pillar at O-3 quarters	1	x	6	1.25	1.50	2.20	24.75					
		1	x	4	0.75	1.50	2.20	9.90					
1.7	Pillar at Hospital	1	x	6	0.65	1.50	1.70	9.95					
		1	x	4	0.50	1.50	1.70	5.10					
1.8	Pillar at Q-5 block	1	x	6	0.50	1.50	1.70	7.65					
		1	x	4	0.50	1.50	1.70	5.10					
1.9	All feed pillar stands with ISA 50x50mm	4	x	8	0.05	1.50	0.50	1.20					
1.9	ISMB-200mm at 33KV-web face	4	x	2	0.16	1.50	7.00	13.44					
	ISMB-200mm at 33KV-flange face	4	x	4	0.10	1.50	7.00	16.80					
1.10	ISMC-100mm at 33KV-web	14	x	2	0.10	1.50	6.00	25.20					
	ISMC-100mm at 33KV-Flange	14	x	4	0.05	1.50	6.00	25.20					
1.10	ISMC-100mm at 33KV-web	6	x	2	0.10	1.50	11.50	20.70					
	ISMC-100mm at 33KV-Flange	6	x	4	0.05	1.50	11.50	20.70					
1.10	ISMC-100mm at 33KV-web	14	x	2	0.10	1.50	5.00	21.00					
	ISMC-100mm at 33KV-Flange	14	x	4	0.05	1.50	5.00	21.00					
1.9	ISMB-125mm at 33KV-web face	6	x	2	0.09	1.50	6.00	9.72					
	ISMB-125mm at 33KV-flange face	6	x	4	0.08	1.50	6.00	16.20					
								426.86	sq.mt	144	1	sq.mt	61468
2	Providing and fixing of carpentry fixtures of all make with screws etc, complete for finished item of work												
	Aldrop	1	x	1	10.00	-	-	10.00	nos	331	1	nos	3310

3	Fabrication and erection of 16 SWG CRCA sheet steel enclosure for power control cubicle panel / boxes etc., including cutting, bending drilling, welding and reveting etc., complete with cleaning with 7 tank process and painting with powder coating including cost and conveyance of all materials and labour charges-Elec-6.2.2												
	Sheet	1	x	1	3.00	3.00	-	9.00	sq.mt	3706	1	sq.mt	33354
4	Supply & application of one coat water based cement primer of interior grade I and two coats of acrylic emulsion paint having VOC (Volatile Organic Compound) content less than 50 grams/litre for internal walls including cost and conveyance of all materials to site, sales & other taxes, incidental, operational and all labour charges etc., and overheads & contractors profit complete for finished item of work in all floors.												
	for walls	1	x	4	13.00	-	4.50	234.00	sq.mt	143	1	sq.mt	33462
	for beams	3	x	3	13.00	-	0.80	93.60	sq.mt	143	1	sq.mt	13385
5	Providing 110 mm Dia ISI marked PVC down water take pipes with socket , 2.5mm thick 4.0 kg/sq.cm pressure of ISI marked including cost of necessary PVC Bends, shoes, iron / PVC clamps and all other accessories and fixing in position including cost and conveyance of all materials, sales & other taxes on materials to site, operational & incidental charges including all labour charges for fixing at site etc., and overheads & contractors profit complete for finished item of work. (APSS No. 1328)												
	at Sub station-4 for rain water lines	1	x	2	4.50	-	-	9.00	Rmt	280	1	Rmt	2520
	Total												
6	Add GST 12%									12%			
7	TOTAL ESTIMATE COST												

Authorized Signature & Stamp

PRICE BID

Name of work: PROVIDING PAINTING WORKS FOR TRANSFORMER YARDS AND SUBSTATIONS AT RGUKT, NUZVID.

Estimated contract value (in figures & words) : Rs.

(in words)

I Sri / Smt./M/s. _____, do hereby express my willingness to execute the aforesaid work as per the conditions, standards, specifications, rules, regulations, etc., stipulated in the tender documents at an overall tender percentage of () % () the estimated contract value (ECV).

SIGNATURE:

NAME OF THE CONTRACTOR /:

AUTHORISED SIGNATORY.