



RAJIV GANDHI UNIVERSITY OF KNOWLEDGE TECHNOLOGIES

(A.P Government Act 18 of 2008)

Nuzvid, RGUKT-campus, Krishna District, Andhra Pradesh-521202

Tele No: 08656-235557.

E-mail Id: ao.nuz@rgukt.in

Ref. No: RGUKT/NUZ/Proc/NIQ/Civil /OHST/18-19

Date: 01.11.2018

To

All Interested vendors

Dear Sir/ Madam,

SUB: NOTICE INVITING QUOTATION FOR EXECUTION WORKS- PROVIDING OF PRECAST COVER SLAB OVER OHST (OVER HEAD STORAGE TANKS) AT BUILDINGS in RGUKT – NUZVID.

Technical Bid

The Administrative Officer, RGUKT- Nuzvid invites quotations for precast cover slab over OHST (over head storage tanks) at all Buildings - RGUKT- Nuzvid, in Single bid as indicated, in sealed cover. Kindly quote your lowest price including labour charges, taxes & transportation.

The Details are as follows:-

- 1. Providing of TMT-Vizag/tata/Jindal/ISI.**
- 2. Providing of nominal mix M-20 grade.**
- 3. Providing of 12mm thick plastering single coat in CM[1:5]**

Please Note-

01. The following must be clearly written on the outer sealed cover irrespective of single bid. Without sealed cover, the quotation will not be accepted.

QUOTATION FOR EXECUTING OF CIVIL WORKs IN RGUKT- NUZVID
NIQREF NO:RGUKT/NUZ/Proc/NIQ/CIVIL/OHST/18-19 Date: 01.11.2018

To
The ADMINISTRATIVE OFFICER
RGUKT – NUZVID
KRISHNA (DIST) – A.P. – 521202

02. There is no Quotation document fee and Quotation document is to be downloaded from our website given below. www.rguktnuz.in/tenders or www.rguktn.ac.in/tenders
03. **Validity:** Quoted rates must valid for 120 days
04. **Delivery:** Unless otherwise stated delivery of goods at RGUKT-Nuzvid, will have to be maximum within **20days**

05. **Firm Registration Document and PAN Account No.** copy of the document to be furnished
06. **GST.No** must appear in the Invoice/Bill
07. All aspects of safe delivery shall be the exclusive responsibility of the vendor
08. **Late and delayed quotation:** Late and delayed tender will not be considered. In case any unscheduled holiday occurs on prescribed closing/opening date, the next working day shall be the prescribed date of closing/opening.
09. **Bid not transferable:** The bid documents are not transferable and the seal and signature of the authorized official of the firm's must appear on all the papers and envelopes submitted.
01. **Payment:** Payment will be made within 30 days from the billing date after getting satisfaction certificate from the concerned department. Payment would be made through online mode only: -
 - (a) Name of the Firm with complete postal address
 - (b) ACCOUNT No
 - (c) Name of the Bank with Branch where the Account exist
 - (d) IFSC CODE
 - (e) PAN No:
02. Kindly read both the Instructions and **Terms & conditions** properly and see that instructions and terms are fully understood and complied. No correspondence/communication shall be entertained in case your quotation is rejected on ground of not complying with our instructions, terms and conditions. **For any clarifications please contact us at 8333981200.**
03. **The contractor/bidder should quote the price bid in percentage on overall tender value.**
04. **No modification/deviations admissible in price bid and Technical bid**
05. **INSTRUCTION TO BIDDERS**
 - (i) Last date & Time of receipt of Tender: **15.11.2018, (1700 HRS)**
 - (ii) Time of opening Tender: **16.11.2018, (1500 HRS)**
 - (iii) Venue of Bid opening: Office of the Administrative Officer's, RGUKT- Nuzvid.

Sd/-

Administrative Officer

Bill of quantities

PROVIDING OF PRECAST COVER SLAB OVER OHST OF ALL BUILDINGS

S.N	Description of Item	Measurements							Contents	Unit	Rate	Per	Amount
		No.		L	B	D							
1	Providing Thermo Mechanically Treated (TMT) (Fe 500 grade as per IS 1786-1979) of different diameters for RCC works , including labour charges for straightening, cutting, bending to required sizes and shapes, placing in position with cover blocks of approved materials and size and tying and lap-splicing with binding wire of 18 SWG, forming grills for reinforcement work as per approved designs and drawings, including cost and conveyance of steel bars, including all wastages such as overlaps, couplings, chairs, spacer bars including cost and conveyance of binding wire, cover blocks and all incidental, operational, labour charges such as cutting, bending, placing in position, tying including sales and other taxes on all materials etc. ,and overheads & contractors profit complete for finished item of work.(APSS No.126)												
				L	Wt								
	at M-1 block @ 150mm c/c	4	x	5	0.79	0.40	-	6.24					
	at M-2 block @ 150mm c/c	4	x	5	0.79	0.40	-	6.24					
	at N-3 block @ 150mm c/c	4	x	6	0.86	0.40	-	8.15					
	at N-4 block @ 150mm c/c	4	x	5	0.79	0.40	-	6.24					
	at O-1 block @ 150mm c/c	4	x	6	0.86	0.40	-	8.15					
	at O-2 block @ 150mm c/c	4	x	5	0.79	0.40	-	6.24					
	at O-3 block @ 150mm c/c	4	x	5	0.76	0.40	-	6.00					
	at O-4 block @ 150mm c/c	4	x	5	0.79	0.40	-	6.24					
	at P-1 block @ 150mm c/c	8	x	6	0.81	0.40	-	15.36					
	at P-2 block @ 150mm c/c	8	x	6	0.86	0.40	-	16.31					
	at P-3 block @ 150mm c/c	8	x	6	0.94	0.40	-	17.83					
	at I-1 SW corner @ 150mm c/c	4	x	5	0.74	0.40	-	5.85					
	at I-1 NE corner @ 150mm c/c	4	x	5	0.74	0.40	-	5.85					
	at I-2 NW corner @ 150mm c/c	4	x	5	0.74	0.40	-	5.85					
	at K-3 NW corner @ 150mm c/c	4	x	5	0.74	0.40	-	5.85					
	at K-3 SW corner @ 150mm c/c	4	x	5	0.74	0.40	-	5.85					
	at A-2 block @ 150mm c/c	8	x	5	0.74	0.40	-	11.69					
	at A-3 block @ 150mm c/c	8	x	5	0.74	0.40	-	11.69					
	at A-4 block @ 150mm c/c	8	x	5	0.74	0.40	-	11.69					
								167.32	Kg	67.2	1 Kg	11244	
2	Supply and placing of the Nominal Mix Concrete M 20 grade corresponding to IS 456 with minimum cement content of 350 kgs per 1 cum of concrete using WEIGH BATCHER / MIXER with 10mm size graded machine crushed hard granite metal(coarse aggregate - as per IS 383 - 1970 and IS 2386 Part 1 to Part 8) from approved quarry including cost and conveyance of all materials like cement, fine aggregate (sand) coarse aggregate, water etc., to site and sales & other taxes on all materials, centering using Casurina Ballies, Bamboos, Wooden Reapers, Runners, Wood Posts, Wall Plates etc., including all operational, incidental and labour charges such as weigh batching, machine mixing, lifting of concrete manually, laying concrete, vibrating, curing, overheads & contractors profit etc., complete but excluding cost of steel and its fabrication charges for finished item of work (APSS No. 402) -75mm thick slab												
	at M-1 block	1	x	2	0.75	0.75	-	1.13					
	at M-2 block	1	x	2	0.75	0.75	-	1.13					

	at N-3 block	1	x	2	0.82	0.82	-	1.34					
	at N-4 block	1	x	2	0.75	0.75	-	1.13					
	at O-1 block	1	x	2	0.82	0.82	-	1.34					
	at O-2 block	1	x	2	0.75	0.75	-	1.13					
	at O-3 block	1	x	2	0.72	0.72	-	1.04					
	at O-4 block	1	x	2	0.75	0.75	-	1.13					
	at P-1 block	2	x	2	0.77	0.77	-	2.37					
	at P-2 block	2	x	2	0.82	0.82	-	2.69					
	at P-3 block	2	x	2	0.90	0.90	-	3.24					
	at I-1 SW corner	1	x	2	0.74	0.40	-	0.58					
	at I-1 NE corner	1	x	2	0.74	0.40	-	0.58					
	at I-2 NW corner	1	x	2	0.74	0.40	-	0.58					
	at K-3 NW corner	1	x	2	0.74	0.40	-	0.58					
	at K-3 SW corner	1	x	2	0.74	0.40	-	0.58					
	at A-2 block	1	x	2	0.74	0.40	-	0.58					
	at A-3 block	1	x	2	0.74	0.40	-	0.58					
	at A-4 block	1	x	2	0.74	0.40	-	0.58					
								22.31	s q. m t	800	1	s q. m t	17848
3	Total												
4	Add 12% GST							12%					
5	Total Estimated Cost												

Authorized Signature & Stamp

PRICE BID

Name of work: CONSTRUCTION OF FOUNDATION FOR RELOCATED GENERATOR AT QUARTERS

Estimated contract value (in figures & words) : Rs.

(in words)

I Sri / Smt./M/s. _____, do hereby express my willingness to execute the aforesaid work as per the conditions, standards, specifications, rules, regulations, etc., stipulated in the tender documents at an overall tender percentage of () % () the estimated contract value (ECV).

SIGNATURE:

NAME OF THE CONTRACTOR /:

AUTHORISED SIGNATORY.