



RAJIV GANDHI UNIVERSITY OF KNOWLEDGE TECHNOLOGIES

(A.P Government Act 18 of 2008)

Nuzvid, RGUKT-campus, Krishna District, Andhra Pradesh-521202

Tele No: 08656-235557.

E-mail Id: ao.nuz@rgukt.in

Ref. No: RGUKT/NUZ/Proc/NIQ/Civil /RW/Hospital Building/18-19 Date: 19.11.2018

To
All Interested vendors

Dear Sir/ Madam,

SUB: NOTICE INVITING QUOTATION FOR EXECUTION WORKS- EXECUTION OF REPAIR WORKS AT HOSPITAL BUILDING in RGUKT – NUZVID.

Technical Bid

The Administrative Officer, RGUKT- Nuzvid invites quotations for Execution of repair works at hospital building - RGUKT- Nuzvid, in Single bid as indicated, in sealed cover. Kindly quote your lowest price including labour charges, taxes & transportation.

The Details are as follows:-

- 1. Removal of damaged doors and frames.**
- 2. Providing of brick masonry for panel with CM 1:5 230 mm thick**
- 3. Providing of reinforced brick masonry for partition wall 110 mm thick CM1:4**
- 4. Plastering 12mm thick single coat with CM 1:5**
- 5. Providing of prelam solid PVC door frame and shutter with 30mm thick.**
- 6. Providing with 400mm x 400mm size non skid ceramic tiles**
- 7. Providing of emulsion.**
- 8. Supplying of 4mm pinheaded window glass.**

Please Note-

01. The following must be clearly written on the outer sealed cover irrespective of single bid. Without sealed cover, the quotation will not be accepted.

QUOTATION FOR EXECUTING OF CIVIL WORKs IN RGUKT- NUZVID
NIQREF NO:RGUKT/NUZ/Proc/NIQ/CIVIL/RW/HOSPITAL BUILDING/18-19 Date:19.11.2018

To
The ADMINISTRATIVE OFFICER
RGUKT – NUZVID
KRISHNA (DIST) – A.P. – 521202

02. There is no Quotation document fee and Quotation document is to be downloaded from our website given below. www.rguktnuz.in/tenders or www.rguktn.ac.in/tenders

03. **Validity:** Quoted rates must valid for 120 days
04. **Delivery:** Unless otherwise stated delivery of goods at RGUKT-Nuzvid, will have to be maximum within **20days**
05. **Firm Registration Document and PAN Account No.** copy of the document to be furnished
06. **GST.No** must appear in the Invoice/Bill
07. All aspects of safe delivery shall be the exclusive responsibility of the vendor
08. **Late and delayed quotation:** Late and delayed tender will not be considered. In case any unscheduled holiday occurs on prescribed closing/opening date, the next working day shall be the prescribed date of closing/opening.
09. **Bid not transferable:** The bid documents are not transferable and the seal and signature of the authorized official of the firm's must appear on all the papers and envelopes submitted.
01. **Payment:** Payment will be made within 30 days from the billing date after getting satisfaction certificate from the concerned department. Payment would be made through online mode only: -
 - (a) Name of the Firm with complete postal address
 - (b) ACCOUNT No
 - (c) Name of the Bank with Branch where the Account exist
 - (d) IFSC CODE
 - (e) PAN No:
- 02.** Kindly read both the Instructions and **Terms & conditions** properly and see that instructions and terms are fully understood and complied. No correspondence/communication shall be entertained in case your quotation is rejected on ground of not complying with our instructions, terms and conditions. **For any clarifications please contact us at 8333981200.**
- 03.** **The contractor/bidder should quote the price bid in percentage on overall tender value.**
- 04.** **No modification/deviations admissible in price bid and Technical bid**
- 05. INSTRUCTION TO BIDDERS**
 - (i) Last date & Time of receipt of Tender: **26.11.2018, (1700 HRS)**
 - (ii) Time of opening Tender: **27.11.2018, (1500 HRS)**
 - (iii) Venue of Bid opening: Office of the Administrative Officer's, RGUKT- Nuzvid.

Sd/-

Administrative Officer

Bill of quantities

REPAIRING WORKS IN HOSPITAL BUILDING													
S.No.	Description of Item	Measurements						Contents	Unit	Rate	Per	Amount	
		No.		L	B	D							
1	Dismantling, clearing away and carefully stacking useful materials for re-use and disposal of unserviceable materials with 100m lead as directed by Executive Engineer duly taking actual premeasurements before dismantling including all labour charges , overheads & contractor profit etc., complete												
	at madicine store main room	1	x	2	0.40	0.20	2.10	0.34					
	emergency ward bathroom door	1	x	2	0.40	0.20	2.10	0.34					
	Male bathroom doors	3	x	2	0.40	0.20	2.10	1.01					
	Female bathroom doors	3	x	2	0.40	0.20	2.10	1.01					
	Female toile block mian door	1	x	2	0.40	0.20	2.10	0.34					
	Female ward main door	1	x	2	0.40	0.20	2.10	0.34					
								3.38	cum	200	1	cum	676
2	Dismantling, clearing away and carefully stacking useful materials for re-use and disposal of unserviceable materials with 100m lead as directed by Executive Engineer duly taking actual premeasurements before dismantling including all labour charges , overheads & contractor profit etc., complete												
	damaged floor tiles	1	x	40	0.40	0.40	-	6.40					
	plastering at doctor room	1	x	1	6.00	-	0.30	1.80					
								8.20	sq.mt	7	1	sq.mt	57
3	Dismantling doors , windows and clear storey windows, Ventilators etc., (wood or steel) shutters including Chowkhats , architraves,hold fasts and other attachments etc., and stacking them within 100m lead including labour charge etc., and overheads & contractors profit complete for finished item of work												
	at madicine store main room	1	x	2	-	-	-	2.00					
	emergency ward bathroom door	1	x	2	-	-	-	2.00					
	Male bathroom doors	3	x	2	-	-	-	6.00					
	Female bathroom doors	3	x	2	-	-	-	6.00					
	Female toilet block mian door	1	x	2	-	-	-	2.00					
	Female ward main door	1	x	2	-	-	-	2.00					
								20.00	each	181	1	each	3620
4	Brick masonry for panel walls in superstructure with CM (1:5) prop: (Cement : Sand) using common burnt clay bricks of class as per Table- I of IS:1077-1992, Non- Modular or traditional size 23 x 11 x 7 cms from approved source having minimum crushing strength of 40 Kg/Sqcm. including cost and conveyance of all materials like cement, screened sand, bricks, water etc., to site, including sales & other taxes on all materials and such as labour charges, like mixing cement mortar, scaffolding charges, constructing masonry, lift charges, curing, etc.,and overheads & contractors profit complete for finished item of work. (APSS No. 501 & 504).												
	at medicine store room	1	x	2	0.30	0.23	2.10	0.29					
	Female toilet block mian door	1	x	2	0.30	0.23	2.10	0.29					
	Female ward main door	1	x	2	0.30	0.23	2.10	0.29					
								0.87	cum	4926	1	cum	4286

5	Reinforced Brick Masonry for partition walls (11.0 cm thick) in CM (1:4) prop. (Cement : Sand) using common burnt clay bricks of class as per Table- I of IS:1077-1992, Non- Modular or traditional size 23 x 11 x 7 cms from approved source having minimum crushing strength of 40 Kg/Sq.cm and placing 2 Nos. of 6mm M.S plain rods in every third layer with free ends of the reinforcement pegged into mortar joints of main brick walls where applicable including cost and conveyance of all materials like cement, steel, sand, bricks, water etc., to site, including sales & other taxes on all materials, all operational, incidental charges such as labour charges for mixing cement mortar, scaffolding charges, constructing masonry, lift charges, curing, etc., and overheads & contractors profit but excluding cost of steel and its fabrication charges complete for finished item of work. (APSS No. of 501 & 509)													
	emergency ward bathroom door	3	x	2	0.30	-	2.10	3.78						
	Male bathroom doors	3	x	2	0.30	-	2.10	3.78						
	Female bathroom doors	1	x	2	0.30	-	2.10	1.26						
								8.82	sq.mt	651	1	sq.mt	5742	
6	Plastering 12mm thick single coat in CM(1:5) using screened sand including cost and conveyance of all materials like cement, sand, water etc., to site, including sales & other taxes on all materials, and all operational, incidental charges on materials and including cost of all labour charges for mixing mortar, finishing, curing as directed by Engineer-in-charge etc., and overheads & contractors profit complete for finished item of work.(SS 901,903 & 904)													
	at medicine store room	1	x	2	0.30	-	2.10	1.26						
	Female toilet block mian door	1	x	2	0.30	-	2.10	1.26						
	Female ward main door	1	x	2	0.30	-	2.10	1.26						
	emergency ward bathroom door	6	x	2	0.30	-	2.10	7.56						
	Male bathroom doors	6	x	2	0.30	-	2.10	7.56						
	Female bathroom doors	1	x	2	0.30	-	2.10	1.26						
								16.38	sq.mt	289	1	sq.mt	4734	
7	SINGLE SIDE PRELAM SOLID PANEL PVC DOOR FRAME (CHOUKHAT): Providing and fixing factory made Pac single side Prelam door frame of the size 50X47 mm with a wall thickness of 5mm, made out of extruded 5mm rigid Pac single side prelam sheet, meter cut at two corners and joined with 2nos. of 150mm long brackets of 1515mm MS.Square tube. The two vertical door profiles are to be reinforced with 19X19mm MS. square tube of 19guage. The door frame shall be fixed to the wall using 65/100mm long MS. Screws through the frame by using Pac fasteners. a minimum of 4nos. of screws to be provided for each vertical member and minimum 2nos. for horizontal member etc. complete as per manufacture specification and direction of Engineer-incharge.													
	at medicine store room	1	x	1	5.20	-	2.10	10.92						
	Female toilet block mian door	1	x	1	5.20	-	2.10	10.92						
	Female ward main door	1	x	1	5.20	-	2.10	10.92						
	emergency ward bathroom door	1	x	3	5.00	-	2.10	31.50						
	Male bathroom doors	1	x	3	5.00	-	2.10	31.50						
	Female bathroom doors	1	x	1	5.00	-	2.10	10.50						
								106.26	Rmt	393	1	Rmt	41760	

8	Providing and fixing 30mm thick BRAND FACTORY MADE BOTHSIDE PRELAM SOLID PANEL PVC DOOR SHUTTER consisting of frame made out of MS. Tubes of 19gauge thickness and size of 19mmX19mm for stiles, top and bottom rails. MS. Frame shall have a coat of steel primers of approved make and manufacture. MS. Frame covered with 5mm thick heat moulded "Rajshri" Prelam Pac 'C' channel of size 30mm thickness, 70mm width out of which 50mm shall be flat and 20mm shall be tapered in 450 angle on either side forming stiles; and 5mm thick, 95mm wide Rajshri Prelam Pac sheet out of which 75mm shall be flat and 20mm shall be tapered in 450 on the inner side to form top and bottom rail 115mm wide Rajshri Prelam Pac sheet out of which 75mm shall be flat and 20mm shall be tapered on both sides to form lock rail. Top, bottom and lock rail shall be provided either side of the panel. 10mm (5mmX2) thick, 20mmwide cross Pac sheet shall be provided as gap insert for top and bottom rail. Panelling of 5mm thick both side Prelam Pac sheet to be fitted in the MS. Frame welded/ sealed to the stiles & rails with 7mm(5mm+2mm) thick X 15mm wide Pac sheet beading on inner side, and joined together with solvent cement adhesive etc. an additional 5mm thick Pac strip of 20mm width is to be stuck on the interior side of the 'C' channel using Pac solvent cement adhesive etc. complete as per direction of Engineer – in-charge, manufacture specification and drawing.												
	at medicine store room	1	x	1	1.00	-	2.10	2.10					
	Female toilet block mian door	1	x	1	1.00	-	2.10	2.10					
	Female ward main door	1	x	1	1.00	-	2.10	2.10					
	emergency ward bathroom door	1	x	3	0.76	-	2.10	4.79					
	Male bathroom doors	1	x	3	0.76	-	2.10	4.79					
	Female bathroom doors	1	x	1	0.76	-	2.10	1.60					
								17.48	sq.mt	3819	1	sq.mt	66756
9	Flooring with Non-skid red or white full body Ceramic floor tiles of size 400 x 400 mm and thickness between 7-8 mm 1st quality conforming to IS:13711, IS:13712, IS:13630 (Parts 1 to 15) of any colour and finish in all shades and designs as per the approved flooring pattern as directed by the Engineer-In -Charge, laying tiles using spacers of 2mm thick, set over base coat of cement mortar (1:8), 12mm thick using screened sand over CC bed already laid or RCC roof slab, including neat cement slurry of honey like consistency spread @ 3.3 Kgs per sqm & jointed neatly with white cement paste to full depth mixed with pigment of matching shade, including cost of all materials like cement, screened sand , water and tiles etc., and overheads & contractors profit complete for finished item of work. (APSS No.701 & 707)												
	floor tiles	1	x	40	0.40	0.4	-	6.40	sq.mt	869	1	sq.mt	5562
10	Supply & application of one coat water based cement primer of interior grade I and two coats of acrylic emulsion paint having VOC (Volatile Organic Compound) content less than 50 grams/litre for internal walls including cost and conveyance of all materials to site, sales & other taxes, incidental, operational and all labour charges etc., and overheads & contractors profit complete for finished item of work in all floors.												
	at plastering location	1	x	1	6.00	-	0.30	1.80	sq.mt	143	1	sq.mt	257
11	Providing dadoing to walls with glazed red or white full body ceramic wall tiles of size 200 x 300 mm / 245 mm x 325 mm and thickness 6 mm 1st quality conforming to IS:13711, IS:13712, IS:13630 (Parts 1 to 15) of any colour and finish in all shades and designs with borders as approved by Engineer-in-Charge set over base coat of CM(1:5) 12 mm thick using screened sand with cement slurry of honey like consistency spread at the rate of 3.30 kgs per sqm and jointing with white cement paste mixed with pigment of matching shade to full depth, including cost of all materials like tiles, cement, sand and water etc., and overheads & contractors profit complete for finished item of work.												
	emergency ward bathroom door	3	x	2	0.30	-	2.10	3.78					
	Male bathroom doors	3	x	2	0.30	-	2.10	3.78					
	Female bathroom doors	1	x	2	0.30	-	2.10	1.26					
								8.82	sq.mt	537	1	sq.mt	4736
12	Supplying & fixing of pin headed window galls including beading, glass panes of any thickness to the existing door/window panes including fixing the beading												
	for outer window glass	1	x	15	0.45	-	1.00	6.75					

	formiddle window glass	1	x	10	0.55	-	1.00	5.50					
								12.25	sq.mt	602	1	sq.mt	7375
	Total												
13	Add GST 12%									12%			
14	TOTAL ESTIMATE COST												

Authorized Signature & Stamp

PRICE BID

Name of work: CONSTRUCTION OF FOUNDATION FOR RELOCATED GENERATOR AT QUARTERS

Estimated contract value (in figures & words) : Rs.

(in words)

I Sri / Smt./M/s. _____, do hereby express my willingness to execute the aforesaid work as per the conditions, standards, specifications, rules, regulations, etc., stipulated in the tender documents at an overall tender percentage of () % () the estimated contract value (ECV).

SIGNATURE:

NAME OF THE CONTRACTOR /:

AUTHORISED SIGNATORY.